

Roofing Estimate

Customer Name Mr. & Mrs. Homeowner February 12, 2008
Address 1 Main St.
City/St/Zip Anywhere CA 95126

Owner Name Mr. & Mrs. Homeowner
Job Address 1 Main St.
Job City/St/Zip Anywhere CA 95126

Type of Roofs

Shake

Heavy Shake \$20,499.41
Medium Shake \$17,963.48
Fire Free Shake \$21,910.82
Fire Free Slate \$21,910.82

Tile

Lightweight Tile \$16,438.19

Composition

CertainTeed Presidential TL \$13,926.18
CertainTeed Landmark TL \$11,900.67
CertainTeed Presidential \$12,394.70
GAF-ELK Lifetime Dimensional \$10,496.76
GAF-ELK 40 Year Dimensional \$9,797.12
GAF-ELK 30 Year Dimensional \$9,298.14
20 Year 3 Tab \$8,795.53

Flat Roofing

Torch Down \$0.00
Single Ply \$0.00

Gutters

Aluminum Pre Painted Seamless \$1,675.14
Galvanized (Bonderized) \$1,919.05
Number of Downspouts 5

The above estimate by Rossetta's Roofing includes the following unless otherwise noted:

Obtain permit from local building department and applicable inspections at the time of installation

Number of roofs to be removed: 2

The installation of 1/2 inch CDX Plywood over existing skip sheathing

The installation of all new nosing over all gable edges, if necessary.

The installation of one layer 36" 30# felt underlayment. (two layers for tile installation)

The installation of all new 26ga. galvanized valley, plumbing vents, and U.L. listed heater vent flashings.

All flashings to be painted with rust proof paint.

The installation of your new roof according to the city and manufacturers recommended procedures.

The installation of all new appropriate ridge shingles on all hips and ridges.

Clean up and haul away all resulting debris.

Estimates written by Rossetta's Roofing may be withdrawn if not accepted within thirty days.

Written contracts will be mailed upon request.

A conditional release will be provided with the final invoice if requested .

If you have any questions, please feel free to contact our office.

Thank you for allowing Rossetta's Roofing to estimate your home.

Estimated by: Tony Cardoso

Summary Sheet

TRAVEL INFORMATION

Number of Miles to Job Site	25
Number of Expected Trips to Job Site	6

PERMIT INFORMATION

No flat roof permit has been estimated	
Pitched Roof Permit	Yes

TEAR-OFF INFORMATION

No flat roofing tear off estimated	
Number of roofs to be removed	2
# Sq 3/12 - 6/12	25

SHEET METAL INFORMATION

Pitched Roofing Metals

1 1/2 - 4 inch plumbing vents	6
3 inch - 10inch HVA	4

SHEETING INFORMATION

Number of Squares to be Sheeted	25
Plywood	
4-6/12	25

FLAT ROOFING METALS

No flat roofing sheetmetal estimated

ROOFING INFORMATION

No flat roofing estimated	
Total Number of Squares to Roof	25
4-6/12	25

GRACE ICE & WATER

No Grace Ice & Water estimated

GUTTER INFORMATION

Gutter Footage	188
1 Story D/S	5
No 2 story downspouts estimated	
No deluxe gutter guard estimated	

MISC. INCREASES

No increases have been added

WARNINGS

You've selected multiple layers being torn off but have not input any squares for Layer 2 in the tear off section
Tear-off squares versus roofing squares does not match
You have not accounted for any attic ventilation